



Project name: WBG Devices-Based Matrix Converter

Team members: Jack Alagood, Kyle Bedrich, lan Farrar



#### **Problem Statement**

- The rise of energy-intensive computing (AI model training, cloud computing, data centers, etc.) creates a need to optimize power delivery to these loads
- Though many solutions have been presented, there remains room for improvement in efficiency and cost






#### **Proposed Solution**

- GaN technology promises greater power density than SiC
- Matrix converters offer bidirectional power flow, adjustable input power factor, and greater power density due to less storage elements






### **System Diagram**





#### **Project Timeline**






### **Subsystem 1 (Primary Side)**

**Jack Alagood** 

Accomplishments since last update	Ongoing progress/problems and plans until the next presentation			
<ul> <li>Finalized PCB (traces, pours, labels, etc.)</li> </ul>	<ul> <li>Assemble board</li> <li>Test incrementally; record measurements</li> </ul>			






### Subsystem 2 (Secondary Side)

**Ian Farrar** 

Accomplishments since last update	Ongoing progress/problems and plans until the next presentation
<ul> <li>Bought Core and Litz Wire</li> <li>Finished Running Simulations</li> </ul>	<ul> <li>Core bought based off datasheets instead of simulation results as planned due to time, so finish analysis of simulation results</li> </ul>



Multilayered transformer model



#### **Subsystem 3 (Controls)**


**Kyle Bedrich** 

## Accomplishments since last update

 Control system validation complete using built-in PLL in software, use of custom PLL with PSIM blocks does not work properly.

# Ongoing progress/problems and plans until the next presentation

 Moving to programming the control system in C instead of using PSIM blocks for better customizability.





#### **Parts Ordering Status**

- Parts ordered
- Board ready to be soldered



#### **Execution/Validation Plans**

ECEN 404	Owner(s)	1/12/2025	1/19/2025	1/26/2025	2/2/2025	2/9/2025	2/16/2025	2/23/2025	3/2/2025
Schematic 3-phase Extension	Jack								
PCB 3-phase Extension	Jack								
Transformer Design	lan								
DSP Debugging	Kyle								
DSP Testing	Kyle								
Simulations	Each								
		3/9/2025	3/16/2025	3/23/2025	3/30/2025	4/6/2025	4/13/2025	4/20/2025	4/27/2025
Transformer Testing	lan								
Board Assembly	Jack								
Board Testing	Group								
Final Presentation	Group								
Final Demo	Group								
Final Report	Group								

Task	Deadline	Status
Schematic 3-phase Extension	1/31/2025	Complete
PCB 3-phase Extension	2/21/2025	Complete
Transformer Design	2/28/2025	Complete
Transformer Testing	3/28/2025	In Progress
DSP Debugging	2/14/2025	Complete
DSP Testing	2/28/2025	Complete
Simulations	3/7/2025	Complete
Board Assembly	3/28/2025	In Progress
Board Testing	4/11/2025	Not Started
Final Presentation	4/16/2025	Not Started
Final Demo	4/26/2025	Not Started
Final Report	4/28/2025	Not Started

Legend
Complete
In Progress
Overdue
Not Started



#### **Thank You**